



GOVERNMENT OF WEST BENGAL
DIRECTORATE OF FORESTS
OFFICE OF THE DIVISIONAL FOREST OFFICER,
WORKING PLAN (SOUTH) -1 DIVISION
Michael Madhusudan Nagar, Midnapore
Paschim Medinipur PIN- 721101
Mail ID: dfowps1@gmail.com, Fax: 03222275363



QUOTATION 36/WP (S) -1 /2018 -19

Sealed quotations addressed to the undersigned by name (**Shri Ayan Ghosh, WBFS**) and not by Designation are invited from the bonafide Contractor for **Extension of Office Building under Working Plans (South) – I Division, Midnapore. M.M.Nagar, Police Line Medinipur.** details of works as given below.

The quotations should reach to this office within **08 .03.2019 up to 2.00 p.m.** without fail. The quotations will be opened tentatively at **3.30 p.m. on 08 .03.2019.** The quotationers may remain present at the time of opening of the quotations papers.

Terms & Condition

1. The quotationers will have to produce valid Income Tax clearance certificate.
2. The credentials should consist of original payment certificate etc. No documents more than 3 years old will be accepted.
3. The undersigned is not bound to accept the lowest rate or any rate quoted may reject any part or all work without assigning any reason.
4. The undersigned reserved the right to demand from the quotationers the clarification and justification against their offer, if required.
5. In case of any dispute the interpretation of the undersigned will be final.
6. The execution of the works as mentioned to the schedule will have to be made within 7(seven) days from issue of the work order.
7. The payment will be made after successful installation.
8. Payment will be made through ECS payment only.
9. Warrenty period please may be mentioned for each item.

(Ayan Ghosh, WBFS)
The Divisional Forest Officer
Working Plans (South) -1 Division
Midnapore

**ESTIMATE FOR FRAME STRUCTURE ROOM
CONSTRUCTION OF OFFICE BUILDING UNDER
DIVISIONAL FOREST OFFICER, WORKING PLAN (SOUTH)-I**

Sl.No.	Description of Item	Quantity	Unit	Rate	Amount
1	Supplying and laying Polythene Sheet (150gm / sq.m.) over damp proof course or below flooring or roof terracing or in foundation or in foundation trenches. (0.85x2.45)	20.78	Sq. M	24	498.72
2	Ordinary Cement concrete (mix 1:1.5:3) with graded stone chips (20 mm nominal size) excluding shuttering and reinforcement if any, in ground floor as per relevant IS codes. (i) Pakur Variety {(0.25x0.3x3x6)+(0.25x0.3x24.45)+(0.125x0.15x24.45)+(0.45x1.5x0.075x5)}x1.54 -0.2	5.850	Cu.M	5900.93	34520.44
3	Reinforcement for reinforced concrete work in all sorts of structures including distribution bars, stirrups, binders etc initial straightening and removal of loose rust (if necessary), cutting to requisite length, hooking and bending to correct shape, placing in proper position and binding with 16 gauge black annealed wire at every intersection, complete as per drawing and direction. (a) For works in foundation and upto roof of ground floor/upto 4 m (5.85x1.259x7850)	0.560	M.T	70784.00	39639.04
4	Hire and labour charges for shuttering with centering and necessary staging upto 4 m using approved stout props and thick hard wood planks of approved thickness with required bracing for concrete slabs, beams and columns, lintels curved or straight including fitting, fixing and striking out after completion of works (upto roof of ground floor) (When the height of a particular floor is more than 4 m the equivalent floor height shall be taken as 4 m and extra for works beyond the initial 4 m ht. shall be allowed under 12 (e) for every 4 m or part thereof) (a) 25 mm to 30 mm thick wooden shuttering as per decision & direction of Engineer-In-Charge.	31.153	Sq.M	321.00	10000.00
	TOTAL				84658.20
5	12% G.S.T				10158.98
	GRAND TOTAL				94817.18
6	1% Cess				948.1718456
	SUPER TOTAL				95765.36
	3% CONTINGENCY				2844.515537
	FINAL TOTAL				98609.87


SAY 98,610.00
(Rupees Ninety Eight Thousand Six Hundred Ten) Only

No. 180 (10) / 2 -11,

Dated 02.03.2019

Copy forwarded with a request to make a wide publicity through their "Notice Board", to:

1. The Sabhadhipati, Paschim Medinipur Zilla Parishad .
2. The Chief Conservator of Forests, MIS, West Bengal.
3. The Conservator of Forests, Working Plan & GIS Circle, West Bengal.
4. The District Magistrate, Paschim Medinipur.
5. The Superintendent of Police, Paschim Medinipur
5. The Sub-Divisional Officer, Sadar, Midnapore.
6. The Executive Engineer, PWD, Paschim Medinipur.
7. The Divisional Forest Officer, Midnapore, Jhargram, Rupnarayan, Kharagpur, Purba Medinipur, Silvi (South) Division & the Divisional Manager, WBFDC, Mid.
8. The District Information Officer, Paschim Medinipur.
9. The Block Development Officer, _____ Block.
10. The Asstt. Divisional Forest Officer, Working Plan (South) – I Division.
11. All Range Officers including AFR, Working Plans (South) – I Division.


Divisional Forest Officer
Working Plans (South) -1 Division
Midnapur
