GOVERNMENT OF WEST BENGAL
DIRECTORATE OF FORESTS
OFFICE OF THE DIVISIONAL FOREST OFFICER,
PANCHET DIVISION
Satyajit Sarani, Bishnupur, Bankura
Phone & Fax No.. 03244-252189, E-mail:Panchetvp@gmail.com,
Website: www.bankuraforest.in

SAVE GREEN SEE DREAM

Quotation No. 28/BLDG/VP/Gr.-D **Dated, Bishnupur, the:16/05/2023**

In terms of Finance Department Audit Branch Govt. of West Bengal's Memorandum No. 5400-F(Y) dated 25-06-2012 sealed quotations are invited from bonafied experienced and reliable resourceful agencies having experience in any Govt. /Semi Govt. / Govt. Under takings for providing various categories services as detailed in schedule below subject to the following conditions.Quotations should be addressed to the undersigned in sealed cover by name as well as official designation ***Sri Anjan Guha, WBFS, Divisional Forest Officer, Panchet Division, Bishnupur.***

SCHEDULE OF WORKS RELATED TO RENOVATION WORK OF GROUP –"D" STAFF QUARTER AT BISHNUPUR HQ BEAT, BISHNUPUR RANGE UNDER, PANCHET DIVISION, BISHNUPUR

Quarter Location: Latitude- N23°03'45.8"&Longitude- E87°18'01.0"

Estimate Copy Enclosed

TERMS AND CONDITIONS

1) The Quotation should be submitted in **sealed cover. Quotation No., Bidder's Name & Address should be properly mentioned on the envelope. Incomplete Quotation paper or documents or envelope will be rejected.**
2) The Contractor should **quote the rates, Percentage (%) in figures as well as in words**.
3) The materials to be supplied must be approved by the concerned Authority.
4) If any defects or issues are found with the supplied materials, they will likely need to be replaced with materials that meet the necessary standards. This is likely to ensure the safety and quality of the materials being used in whatever application they are intended for.
5) **The Contractors should submit Income-Tax, Sales Tax and profession Tax Clearance Certificate, GSTCertificate, PAN, Aadhaar& Trade License. Incomplete Quotation will be summarily rejected.**
6) Acceptance of lowest quotation is not obligatory and the undersigned reserves the right to accept or reject any of all the quotations without assigning any reason whatsoever.
7) **The estimated rate is inclusive of all Taxes, Transportation Cost to the Division Office, Panchet Division. The quotationer should quote their rate accordingly.**
8) **Bill has to be submitted with detail break up of GST (CGST & SGST) as per the prevalent Govt. Order in this respect. All Taxes will be deducted from the gross bill as per Govt. rule**.
9) Sealed Quotation will be received up **to 25/05/2023 & Opened on 26/05/2023 at 11:30 A.M.**

Divisional Forest Officer
Panchet Division
Bishnupur Bankura

No. 1637(2)**/02-08** **Dated, Bishnupur, the: 16/05/2023**

Copy forwarded for information to and wide circulation to :

1. The Divisional Forest Officer, Panchet Division, Bishnupur.
2. The Assistant Divisional Forest Officer, Panchet Division, Bishnupur.
3. The Sub- Divisional Officer, Bishnupur.
4. The Sub- Divisional Information & Cultural Officer, Bishnupur.
5. The Block- Development Officer, Bishnupur.
6. The Chairman, Bishnupur, Municipality
7. The All Range Officers, Panchet Division with request to affix in the Range Notice board.
8. The Computer Operator to uploading 'www.bankuraforest.in' website
9. Office Notice Board

Divisional Forest Officer
Panchet Division
Bishnupur Bankura

Annexure- BL – 1.
Repair and Renovation of Group-D Housing Quarter

(Estimate Prepared as per P.W.D. Schedule of Rate)

Sl. No	Description of items of works	No	Length (M)	Breadth (M)	height (M)	Quantity	Unit	Rate (Rs.)	Amount (Rs.)
1	{ P.W.D/P-81/ Item No. 9}								
	Stripping off worn out plaster and raking out joints of walls, celings etc. upto any height and in any floor including removing rubbish within a lead of 75m as directed.								
		2	6	5		60	Sqm	19	1140.00
2	{ P.W.D./P-189/ Item No. 1}								
	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners, as directed and racking out joints or roughening of concrete surface including throating, nosing and drip course as necessary at ground floor.								
	(i) 20 mm thick plaster.(6:1)								
	room inside	1	6	5		30	Sqm	153	4590.00
	(a) with (1:6) cement mortar. (II) 15 mm. thick plaster. Out side								
		1	6	5		30	Sqm	135	4050.00
3	{ P.W.D./P-114/ Item No. 1}								
	Wood work in door and window frame fitted and fixed in position complete Etc. (a) other local wood								
	D	1	5.2	0.1	0.075	0.039	cum		
	W	1	4.5	0.1	0.075	0.034	cum		
	Total					0.073	cum	36302	2650.05
4	{ P.W.D./P-117/ Item No. 1}								
	Panel shutters of door and window, as per design (each panel consisting of single plank without joint), including fitting and fixing the same in position but excluding the cost of hinge and other fittings. In ground floor. (In case of non-supply of single plank, penal rate of reduction of 20% will be made) (d) Local.								
	D	1	1.2	2.7		3.240	sqm		
	W	1	1.2	1.2		1.440	sqm		
	Total					4.680	sqm	3683	17236.44
5	{ P.W.D./P-140/ Item No. 4}								
	Supplying, fitting and fixing M.S. clamps for door and window frame made of flat bent bar, end bifurcated with necessary screws etc. by cement concrete(1:2:4) as per direction. (Cost of concrete will be paid separately) (a) 40mm X 6mm, 250mm Length								
		20				20	nos	29	580.00

6	{ P.W.D./P-140/ Item No. 5}								
	Iron butt hinges of approved quality fitted and fixed with steel screws, with ISI mark.								
	(ii) 50mm. X 40mm. X 2.5mm.	16				16	nos	26	416.00
	(vi) 100mm. X 50mm. X 1.25mm	6				6	nos	43	258.00
7	{ P.W.D/P-141/ Item No. 10}								
	i) Iron hasp bolt of approved quality fitted and fixed complete (oxidised) with 16mm dia rod with centre bolt and round fitting 300mm long								
		4				4	nos	134	536.00
8	{ P.W.D./P-141/ Item No. 8}								
	Iron socket bolt of approved quality fitted and fixed complete								
	300mm longx10mm dia bolt	2				2	nos	95	190.00
	150mm longx10mm dia bolt	8				8	nos	63	504.00
	(i) 75mm dia.	2				2	nos	28	56.00
9	{ P.W.D./P-104/ Item No. 13}								
	(a) M.S.or W.I. Ornamental grill of approved design joints ontinuously welded with M.S, W.I. Flats and bars of windows, railing etc. fitted and fixed with necessary screws and lugs in ground floor.								
	grill W	2	1.2	1.2		2.880	Sqm		
	Total					2.880	Sqm		
	@ 15kg/ sqm					43.200	kg	72.38	3126.82
10	{ P.W.D./P-158/ Item No. 15}								
	Applying Exterior grade Acrylic primer of approved quality and brand on plastered or cencrete surface old or new surface to receive decorative textured(matt finish) or smooth finish acrylic exterior emulsion paint including scraping and preparing the surface throughly, complete as per manufacturer's specification and as per direction of the EIC								
	A2	1	8.2	9		73.800	sqm	34.04	2512.15
11	{ P.W.D./P-159/ Item No. 19}								
	Protective and Decorative Acrylic exterior emulsion paint of approved quality, as per manufacturer's specification and as per direction of EIC to be applied over acrylic primer as required. The rate includes cost of material, labour, scaffolding and all incidental charges but excluding the cost of primer.								
	a) Normal Acrylic Emulsion				A2	73.800	Sqm	73	5387.40
12	{ P.W.D/P-200/ Item No. 1}								
	(b) Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc.								
	A4	1	2.88	2.88		8.294	sqm	29	240.53

44	{P.W.D./P-200/Item No. 2} (A) Painting with best quality synthetic enamel paint of approved make and brand including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary. (B) On steel or other metal surface With super gloss (hi-gloss)- Total		8.294	Sqm		
	A4		8.294	Sqm	79	655.23
					Total = A (Rs.)	**44128.61**
					Add 12% GST B (Rs.)	**5295.43**
					Sub Total Rs. C	**49424.04**
					Add @1% labour welfare cess on C (Rs.)	**494.24**
					Total Rs. -	**49918.48**
					Or Say -	**49918.00**

Forty Nine Thousand Nine Hundred & Eighteen Only

Divisional Forest Officer
Panchet Division
Bishnupur